




# **Phytoremediation of Landfill Leachate**

# Problem Definition

- 1,754 Municipal solid waste landfills in U.S. (2007)
- Leachate - water percolated through a landfill
  - Can pollute groundwater
  - High COD, ammonia, dissolved solids
  - Must be managed + treated
- Treatment
  - Ship to existing water treatment facility
  - On site chemical/physical process
  - Constructed Wetland
- Alachua County Southwest Landfill
  - Explore on site leachate treatment



# Phycoremediation

- Growing algae as water treatment
  - > Algae uptake nutrients and dissolved solids
  - > Historically associated with polluted water (blooms)
  - > Huge diversity of species
    - Found in fresh & salt waters
- Benefits of Algae
  - > Biomass useful for fertilizers, feedstocks, etc.
  - > Possibility for production of bioenergy
    - Lipids in algae cells




# Energy & Materials

- ◎ Current leachate treatment
  - > Energy sink
  - > Disposal of useful nutrients (N & P compounds)
  - > Leachate as a cost
- ◎ Phycoremediation
  - > Potential energy source
  - > Development of useful nutrient/material cycle
  - > Leachate as a resource



# Alachua County Southwest Landfill

- Opened in 1973, Closed in 1999
- 27 acre Lined cell open from 1988-1999
  - > Operated at ~300 tons/day
  - > Used as experimental bioreactor by UF
    - Leachate circulation & methane production
- Leachate recirculated 1990-1995, 2002-present
  - > 3.7 Million gallons groundwater added 2004-2005
  - > Original pretreatment on site before shipped to GRU wastewater facility



# Phycoprospecting

- Search for algae adapted to landfill conditions
- Examination of bioresource potential
  - Lipids, pigments, etc
- Native polycultures
  - Improved robustness over monocultures








Micro-Tub Experimental Design











# Macro-Slope Experimental Design



## Dilution Test Experimental Design



# Algae Diversity





# Experimental Methods

- **Cell Counts**
  - > Allows count of cells/mL using microscope
- **Conductivity**
  - > Measures ability of sample to carry electrical current
- **Phosphorous**
  - > spectrophotometer, which measures light absorbance, used to test phosphate levels in samples
- **Fluorescence**
  - > Chlorophyll autofluorescence used as a proxy for culture growth
- **Ammonia**
  - > The ammonia test measures the total ammoniacal nitrogen in the sample
- **pH**
  - > Monitored due as its affect on ammonium deprotonation and biology



Above: Ammonia Probe;  
Below: Hemacytometer

pH meter

Above: Fluorimeter  
Below: Conductivity Probe



Phosphorus Setup



# Results Overview

- Fluorescence data for dilution tests
- Cell counts for dilution tests
- Algae diversity in leachate dilutions
- Ammonia data for dilution tests
- Electro conductivity data
- Phosphorus and pH readings for dilution tests
- Dry weight and lipid calculations






Micro Tub	Macro Pool
Concentration 90 percent	Concentration 60 percent
pH 9.00 - 9.27	pH initial 8.5, max 10.24 on 6/11
NH4-N decreased from 133.21 mg NH4-N/L to <1.00 mg NH4-N/L in 12 days and remained	NH4-N mirrored downward trend in micro tub
Cell counts reached peak of $4.25 \times 10^6$ cells/ml on 6/15	Cell count peaked on $1.74 \times 10^6$ cells/ml on 7/21
EC decreased from 5.47 mS/cm on 5/28 to 3.63 mS/cm on 7/9	EC decreased 2.33 mS/cm to 1.55 mS/cm, dramatic increase to 3.18 mS/cm after 3 cm of raw leach ate added
Fluorescence had first peak on 6/15 at 1965.4 RFU to 6191.5 RFU on 7/21	Fluorescence coincides with the addition of leachate peaks on 7/9, max at 20,322.3 RFU on 7/21
PO4 decreased until 6/9, increased until 6/15, significant decrease after	PO4 increased until 6/15, dropped significantly after


# Cell Counts

Cells Counts for Dilution Test



# Fluorescence


Fluorescence Data from Dilution Tests






# Phosphorus

## Orthophosphorous Concentrations for Dilution Tests




# Ammonia

## Dilution Tests: Concentrations of Ammonia




## pH Distribution of Dilution Tests





# Electroconductivity

## Electroconductivity for Dilution Tests



# Conclusions

- ◉ Algae are capable of growing in all dilutions of leachate
  - > 25-50% dilutions exhibited greatest growth and photosynthetic activity
- ◉ Algae shows potential as remediation strategy
  - > Further research necessary on uptake of dissolved ions
  - > More intensive investigation of algae growth in leachate
    - Reproduction, Biomass, Lipid production, etc...
  - > Application at landfills including harvesting

# References

Abeliovich, A. & Azov, Y. (1975). Toxicity of Ammonia to Algae in Sewage Oxidation Ponds. *Applied and Environmental Microbiology*, 31 (6), 801-806.

Azov, Y. and Goldman, J.C. (1981). Free Ammonia Inhibition of Algal Photosynthesis in Intensive Cultures. *Applied and Environmental Microbiology*, 42 (4), 735-739.

Lin, L., Chan, G.Y.S., Jiang, B.L., & Lan, C.Y. (2007). Use of ammoniacal nitrogen tolerant microalgae in landfill leachate treatment. *Waste Management*, 27(2007), 1376-1382.



# QUESTIONS?

